

[illegible]

# 土工計算書（スラロームコース取水口導水路）

| 位 置 | 横 断 面 積 |      |  | 平 均 横 断 面 積 |       |  | 距 離   | 体 積      |          |  |
|-----|---------|------|--|-------------|-------|--|-------|----------|----------|--|
|     | 切土      | 流用盛土 |  | 切土          | 流用盛土  |  |       | 切土       | 流用盛土     |  |
| 800 | 22.9    | 22.9 |  |             |       |  |       |          |          |  |
| 700 | 37.4    | 37.4 |  | 30.15       | 30.15 |  | 100.0 | 3,015.0  | 3,015.0  |  |
| 600 | 32.3    | 32.3 |  | 34.85       | 34.85 |  | 100.0 | 3,485.0  | 3,485.0  |  |
| 500 | 37.1    | 37.1 |  | 34.70       | 34.70 |  | 100.0 | 3,470.0  | 3,470.0  |  |
| 400 | 29.6    | 29.6 |  | 33.35       | 33.35 |  | 100.0 | 3,335.0  | 3,335.0  |  |
| 300 | 42.1    | 42.1 |  | 35.85       | 35.85 |  | 100.0 | 3,585.0  | 3,585.0  |  |
| 300 | 84.2    | 84.2 |  |             |       |  |       |          |          |  |
| 250 | 86.1    | 86.1 |  | 85.15       | 85.15 |  | 50.0  | 4,257.5  | 4,257.5  |  |
|     |         |      |  |             |       |  |       |          |          |  |
|     |         |      |  |             |       |  |       |          |          |  |
|     |         |      |  |             |       |  |       |          |          |  |
| 合計  |         |      |  |             |       |  | 550.0 | 21,147.5 | 21,147.5 |  |

| 土工計算書（スラロームコース） |         |      |  |             |       |  |       |          |          |  |
|-----------------|---------|------|--|-------------|-------|--|-------|----------|----------|--|
| 位 置             | 横 断 面 積 |      |  | 平 均 横 断 面 積 |       |  | 距 離   | 体 積      |          |  |
|                 | 切土      | 流用盛土 |  | 切土          | 流用盛土  |  |       | 切土       | 流用盛土     |  |
| 250             | 39.3    | 39.3 |  |             |       |  |       |          |          |  |
| 200             | 44.5    | 44.5 |  | 41.90       | 41.90 |  | 50.0  | 2,095.0  | 2,095.0  |  |
| 150             | 42.4    | 42.4 |  | 43.45       | 43.45 |  | 50.0  | 2,172.5  | 2,172.5  |  |
| 100             | 46.6    | 46.6 |  | 44.50       | 44.50 |  | 50.0  | 2,225.0  | 2,225.0  |  |
| 50              | 50.8    | 50.8 |  | 48.70       | 48.70 |  | 50.0  | 2,435.0  | 2,435.0  |  |
| 0               | 54.3    | 54.3 |  | 52.55       | 52.55 |  | 50.0  | 2,627.5  | 2,627.5  |  |
| -50             | 24.2    | 24.2 |  | 39.25       | 39.25 |  | 50.0  | 1,962.5  | 1,962.5  |  |
|                 |         |      |  |             |       |  |       |          |          |  |
|                 |         |      |  |             |       |  |       |          |          |  |
|                 |         |      |  |             |       |  |       |          |          |  |
|                 |         |      |  |             |       |  |       |          |          |  |
| 合計              |         |      |  |             |       |  | 300.0 | 13,517.5 | 13,517.5 |  |

# 土工計算書（スラロームフィニッシュ側左岸コース補強切土及び盛土）

| 位 置 | 横 断 面 積 |      |  | 平 均 横 断 面 積 |       |  | 距 離   | 体 積     |         |  |
|-----|---------|------|--|-------------|-------|--|-------|---------|---------|--|
|     | 切土      | 流用盛土 |  | 切土          | 流用盛土  |  |       | 切土      | 流用盛土    |  |
| 50  | 33.0    | 33.0 |  |             |       |  |       |         |         |  |
| 0   | 33.0    | 33.0 |  | 33.00       | 33.00 |  | 50.0  | 1,650.0 | 1,650.0 |  |
| -50 | 33.0    | 33.0 |  | 33.00       | 33.00 |  | 50.0  | 1,650.0 | 1,650.0 |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
|     |         |      |  |             |       |  |       |         |         |  |
| 合計  |         |      |  |             |       |  | 100.0 | 3,300.0 | 3,300.0 |  |